

---

---

सुरक्षा पहचान — बचाव एवं निकास  
योजना संबंधी चिन्ह

**Safety Identification — Escape and  
Evacuation Plan Signs**

ICS 01.080.10

© BIS 2018



भारतीय मानक ब्यूरो  
BUREAU OF INDIAN STANDARDS  
मानक भवन, 9 बहादुरशाह ज़फर मार्ग, नई दिल्ली-110002  
MANAK BHAVAN, 9 BAHADUR SHAH ZAFAR MARG  
NEW DELHI — 110002  
[www.bis.gov.in](http://www.bis.gov.in) [www.standardsbis.in](http://www.standardsbis.in)

## NATIONAL FOREWORD

This Indian Standard which is identical with ISO 23601 : 2009 'Safety identification — Escape and evacuation plan signs' issued by the International Organization for Standardization (ISO) was adopted by the Bureau of Indian Standards on the recommendation of the Basic Standards Sectional Committee and approval of the Production and General Engineering Division Council.

The text of ISO Standard has been approved as suitable for publication as an Indian Standard without deviations. Certain terminology and conventions are however not identical to those used in Indian Standards. Attention is particularly drawn to the following:

- a) Wherever the words 'International Standard' appear referring to this standard, they should be read as 'Indian Standard'.
- b) Comma (,) has been used as a decimal marker while in Indian Standards, the current practice is to use a point (.) as the decimal marker.

In the adopted standard, reference appears to following International Standards for which Indian Standards also exist. The corresponding Indian Standards which is to be substituted in its place are listed below along with its degree of equivalence for the edition indicated

<i>International Standards</i>	<i>Corresponding Indian Standards</i>	<i>Degree of Equivalence</i>
ISO 3864 — 1 : 2002 Graphical symbols — Safety colours and safety signs — Part 1 Design principles for safety signs and safety markings	IS 16449 (Part 1) : 2018 Graphical symbols — Safety colours and safety signs : Part 1 Design principles for safety signs and safety markings	Identical to ISO 3864-1 : 2011
ISO 3864 — 3 Graphical symbols — Safety colours and safety signs — Part 3 : Design principles for graphical symbols for use in safety signs	IS 16449 (Part 3) : 2018 Graphical symbols — Safety colours and safety signs : Part 3 Design principles for graphical symbols for use in safety signs	Identical to ISO 3864-3 : 2012
ISO 7010 Graphical symbols — Safety colours and safety signs — Registered safety signs	IS 16451 : 2018 Graphical symbols — Safety colours and safety signs — Registered safety signs	Identical to ISO 7010 : 2017
ISO 17724 Graphical symbols — Vocabulary	IS 16453 : 2018 Graphical symbols — Vocabulary	Identical to ISO 17724 : 2003

The technical committee has reviewed the provisions of the following International Standards referred in this adopted standard and has decided that they are acceptable for use in conjunction with this standard:

<i>International Standard</i>	<i>Title</i>
ISO 17398 : 2004	Safety colours and safety signs — Classification, performance and durability of safety signs

# *Indian Standard*

## SAFETY IDENTIFICATION — ESCAPE AND EVACUATION PLAN SIGNS

**IMPORTANT** — The electronic file of this document contains colours which are considered to be useful for the correct understanding of the document. Users should therefore consider printing this document using a colour printer.

### 1 Scope

This International Standard establishes design principles for displayed escape plans that contain information relevant to fire safety, escape, evacuation and rescue of the facility's occupants. These plans may also be used by intervention forces in case of emergency.

These plans are intended to be displayed as signs in public areas and workplaces.

This International Standard is not intended to cover the plans to be used by external safety services nor detailed professional technical drawings for use by specialists.

### 2 Normative references

The following referenced documents are indispensable for the application of this document. For dated references, only the edition cited applies. For undated references, the latest edition of the referenced document (including any amendments) applies.

ISO 3864-1:2002, *Graphical symbols — Safety colours and safety signs — Part 1: Design principles for safety signs in workplaces and public areas*

ISO 3864-3, *Graphical symbols — Safety colours and safety signs — Part 3: Design principles for graphical symbols for use in safety signs*

ISO 7010, *Graphical symbols — Safety colours and safety signs — Safety signs used in workplaces and public areas*

ISO 17724, *Graphical symbols — Vocabulary*

ISO 17398, *Safety colours and safety signs — Classification, performance and durability of safety signs*

### 3 Terms and definitions

For the purposes of this document, the terms and definitions given in ISO 17724 and the following apply.

#### 3.1

##### **emergency safety notice**

instructions for occupants, to be followed in case of emergency

**3.2**  
**escape plan**  
plan displayed for the occupants of a facility on which are illustrated the necessary elements for escape and on which may appear information required for evacuation, rescue and for a first intervention

**3.3**  
**escape route**  
designated route to a place of intended safety

**3.4**  
**escape plan detail**  
detailed representation of the area marked in the overview plan based on floor plans

**3.5**  
**fire safety notice**  
instructions for occupants, to be followed in case of fire

**3.6**  
**overview plan**  
simplified graphical representation used to relate the escape plan detail to the overall facility or site

## **4 General**

Before applying the design principles, the fire safety management procedures shall have determined a number of essential elements to be shown on the escape plans. The escape plans shall be a reflection of the study of the following information:

- a) fire safety manuals and procedures;
- b) current site and facility plan drawing(s) with key features of the facility as verified by site visit;
- c) identification of all escape routes;
- d) evacuation planning documentation including expected people movement and any instructions given and the way they are to be given;
- e) location of all fire-fighting equipment and alarms;
- f) location of emergency equipment and evacuation aids;
- g) required actions to be taken in case of emergency or fire;
- h) location of refuge and assembly points.

The purpose of escape plans is to help people orient themselves in relation to the planned escape route. In this way, the escape plan complements the facility's safety way guidance system (see ISO 16069).

## **5 Design requirements**

The escape plan shall be designed in accordance with the evacuation strategy of the facility and addresses the specific needs of the occupants of the premises or part thereof.

The following requirements shall be met by any escape plan.

- a) The exact location of the user shall be indicated on the escape plan.
- b) Escape plans shall use colour.

- c) The scale of the escape plan is dependent on the size of the facility, the level of detail to be illustrated and the intended location of the escape plan. Scales no less than the following shall be used:
- 1:250 for large-sized facilities;
  - 1:100 for small- to medium-sized facilities;
  - 1:350 for plans displayed in individual rooms.

Detailed elements such as stairs or corridors may be drawn to a larger scale to increase conspicuity or to accommodate the placement of safety signs on the escape plan. For a series of escape plans for the same facility, the same scale should be used. For certain specific areas of the facility, e.g. parking areas or technical spaces, other scales may be used to recognize the extent of empty space.

- d) In a set of facility plans, all defined areas shall be illustrated consistently.
- e) In order to achieve sufficient visibility and legibility, the vertical illumination on escape plans shall be no less than 50 lx provided by the normal lighting. Where emergency lighting is provided in case of failure of the normal lighting, the vertical illumination on escape plans comprising ordinary materials or phosphorescent materials shall be no less than 5 lx. Where emergency lighting is not provided in case of failure of the normal lighting or where a phosphorescent safety way guidance system according to ISO 16069 is provided, escape plans comprising phosphorescent materials may be used. In all cases, the phosphorescent material shall be no less than classification C according to ISO 17398.
- f) In order to identify safety colours on the plans, the minimum value for the colour-rendering index,  $R_a$ , from a lamp shall be  $\geq 40$ . The luminaire shall not substantially subtract from this. Where escape plans are based on phosphorescent materials, excitation shall be from white fluorescent lamps. Low-pressure sodium lamps shall not be used.
- g) The background of an escape plan shall have the safety colour white or phosphorescent white as defined in ISO 3864-1:2002, Table 4.
- h) The minimum size of an escape plan shall be 297 mm  $\times$  420 mm (A3) except for escape plans to be located in individual rooms where the plan size may be reduced to 210 mm  $\times$  297 mm (A4). A tolerance of 5 % is acceptable.
- i) Escape plans shall be up to date.
- j) The orientation of the plan as displayed shall be related to the viewer so that locations on the left of the plan are to the viewer's left and locations on the right of the plan are to the viewer's right.
- k) When safe condition and fire-fighting equipment are indicated on the escape plan, they shall use safety signs that are the same as in their installed location in the facility and both shall conform to ISO 7010.
- l) Escape plans shall have a legend.
- m) Escape plans shall have a standardized header, including the words "Escape plan" in the language(s) of the country in which the plan is used.
- n) Escape plans shall show the position of the assembly points as part of the escape plan detail or on an overview plan.

## 6 Size of plan elements

The following requirements shall be met.

- a) Information presented on escape plans shall be legible at the intended viewing distance. The minimum lettering height shall be 2 mm. Fonts should be chosen that maximize the legibility at the intended viewing distance.

- b) The minimum height of the header shall be at least 7 % of the smallest dimension of the escape plan and the height of its characters shall be at least 60 % of the height of the header. Examples are given in Table 1.
- c) Safety signs shown on the plan shall have a minimum height of 7 mm.
- d) The line width for the graphical representation of the facility's structural walls shall be at least 1,6 mm. Interior partition walls shall be represented by lines of a minimum width of 0,6 mm. If detailed elements are shown on the plan (e.g. stairs, shelves, windows), they shall be shown by lines of a minimum width of 0,15 mm.

In the representation of long escape corridors, architectural features or equipment should be shown to give the user a sense of scale/distance.

**Table 1 — Examples of the minimum height of header and characters**

Size of escape plan mm × mm	Height of escape plan mm	Height of header mm	Height of capital letter mm
297 × 420 (A3)	297	21	13
420 × 594 (A2)	420	30	18
594 × 841 (A1)	594	42	26
841 × 1 189 (A0)	841	59	36

## **7 Contents and representation**

### **7.1 Header**

Every escape plan shall have a header. For the header, upper- and lower-case letters may be used.

### **7.2 Overview plan**

Except when a small facility's escape plan detail is itself an overview perspective of the facility, every escape plan shall incorporate an overview plan.

An overview plan shall incorporate:

- a) the assembly point location(s);
- b) the overall facility/site plan with the specific section covered by the escape plan detail highlighted;
- c) a simplified representation of the surrounding area (e.g. roadways, parking areas, other buildings).


The size of the overview plan shall not exceed 10 % of the area of the escape plan.

### **7.3 Escape plan detail**

The escape plan detail shall incorporate:

- a) the floor plan of the relevant part of the facility that is modified to
  - eliminate non-essential details,
  - highlight important elements,
  - increase legibility and ease of comprehension,
  - orient the plan to the position of the viewer;

- b) all emergency exits and escape routes, horizontal and vertical. If directional instructions are to be given from a specific “You are here” point, such directional information shall be conveyed by the use of arrow-type D from ISO 3864-3 (see Figure 1);



**Figure 1 — Arrow indicating the direction of movement of people (ISO 3864-3, arrow-type D)**

- c) the point of location of the user (“You are here”);
- d) the location of stairs;
- e) any specific evacuation provisions made available for people with disabilities;
- f) the location and type of the first intervention fire equipment and emergency and rescue equipment, e.g. fire alarms, fire extinguisher, fire hoses, first aid equipment;

If it is not possible to show the actual location of the safety signs because of the scale used, the safety signs may be shown separately in the closest available free space with a leader line to indicate the correct location (see Figure A.1).

- g) the location of the lifts as an architectural feature.

#### **7.4 Safety notices**

Escape plans shall always be associated with fire and emergency safety notices which may be on the escape plan or displayed in proximity to the escape plan.

#### **7.5 Legend**

The legend shall appear on the escape plan and shall give the meaning of the safety signs, graphical symbols and colour coding used on the escape plan. Examples are given in Annex A.

#### **7.6 Other information**

The following information shall be part of the plan:

- a) plan designer;
- b) name of the facility;
- c) floor designation;
- d) date of plan design and revision number;
- e) plan number.

## **7.7 Use of colours**

### **7.7.1 Escape routes**

Directional arrows shall be in safety green according to ISO 3864-1. Escape routes shall be highlighted in light green which gives sufficient contrast to the arrows.

NOTE With phosphorescent materials, graphical methods such as halftone or hatching of the escape route can be used to render the escape route directional arrows visible in dark conditions.

### **7.7.2 Safety signs**

Safety signs shall be reproduced in safety colours according to ISO 3864-1.

### **7.7.3 Point of location of the user**

The point of location of the user shall be safety blue according to ISO 3864-1.

### **7.7.4 Background colour**

The colour of the background shall be white or phosphorescent white according to ISO 3864-1.

### **7.7.5 Outline of facility structural elements**

The colour of the outline of facility structural elements shall be black.

### **7.7.6 Header**

The header shall be in safety colour green and the text shall be in the contrast colour as given in ISO 3864-1.

### **7.7.7 Text**

The normal colour of the text shall be black. Other colours may be used for highlighting purposes.

## **8 Materials**

Escape plans shall be made of materials and inks that are durable enough to resist the environmental influences at the site of the application (e.g. light resistance and resistance to humidity) for the expected service life. If required, durability characteristics shall be measured by methods described in ISO 17398.

## **9 Installation and location**

Escape plans shall be located so that they are conspicuous in their environment of use and sited to ensure that they are accessible and readable to the intended user.

These plans shall be permanently fixed and are intended to be located

- a) at positions where occupants can learn the means of escape and
- b) at strategic points of the escape route, which can be
  - on every floor at primary entry points,
  - near lifts and stairs,



- in every room, e.g. hotel rooms,
- at appropriate training points, e.g. cafeterias, office centres, meeting places,
- at principal junctions and intersections.

## **10 Inspection and revision**

Inspections of the escape plans shall be conducted at regular intervals, to ensure they are legible, conspicuous, comprehensible and up to date.

Any change of the facility or its fire safety or emergency procedures shall result in a review of the escape plans and, when necessary, revision to the escape plans.

## **Annex A** (informative)

### **Examples of escape plans**

Figures A.1 through A.4 are example layouts of escape plans.

These examples should not be assumed to be exhaustive. They are not drawn to scale.




Figure A.1 — Example of an escape plan without directional arrows — Complete floor




Figure A.2 — Example of an escape plan with directional arrows — Complete floor




Figure A.3 — Example of an escape plan — Part of the floor




Figure A.4 — Example of an escape plan — Complete floor with stairs

## Bibliography

- [1] ISO 216, *Writing paper and certain classes of printed matter — Trimmed sizes — A and B series, and indication of machine direction*
- [2] ISO 16069, *Graphical symbols — Safety signs — Safety way guidance systems (SWGS)*
- [3] ISO 30061, *Emergency lighting*





## Bureau of Indian Standards

BIS is a statutory institution established under the *Bureau of Indian Standards Act, 1986* to promote harmonious development of the activities of standardization, marking and quality certification of goods and attending to connected matters in the country.

### Copyright

BIS has the copyright of all its publications. No part of these publications may be reproduced in any form without the prior permission in writing of BIS. This does not preclude the free use, in the course of implementing the standard, of necessary details, such as symbols and sizes, type or grade designations. Enquiries relating to copyright be addressed to the Director (Publications), BIS.

### Review of Indian Standards

Amendments are issued to standards as the need arises on the basis of comments. Standards are also reviewed periodically; a standard along with amendments is reaffirmed when such review indicates that no changes are needed; if the review indicates that changes are needed, it is taken up for revision. Users of Indian Standards should ascertain that they are in possession of the latest amendments or edition by referring to the latest issue of 'BIS Catalogue' and 'Standards : Monthly Additions'.

This Indian Standard has been developed from Doc No. : PGD 01 (1597).

### Amendments Issued Since Publication

Amend No.	Date of Issue	Text Affected

## BUREAU OF INDIAN STANDARDS

### Headquarters :

Manak Bhavan, 9 Bahadur Shah Zafar Marg, New Delhi 110002  
Telephones : 2323 0131, 2323 3375, 2323 9402 Website : www.bis.org.in

### Regional Offices :

	Telephones
Central : Manak Bhavan, 9 Bahadur Shah Zafar Marg NEW DELHI 110002	{ 2323 7617 2323 3841
Eastern : 1/14 C.I.T. Scheme VII M, V. I. P. Road, Kankurgachi KOLKATA 700054	{ 2337 8499, 2337 8561 2337 8626, 2337 9120
Northern : Plot No. 4-A, Sector 27-B, Madhya Marg, CHANDIGARH 160019	{ 26 50206 265 0290
Southern : C.I.T. Campus, IV Cross Road, CHENNAI 600113	{ 2254 1216, 2254 1442 2254 2519, 2254 2315
Western : Manakalaya, E9 MIDC, Marol, Andheri (East) MUMBAI 400093	{ 2832 9295, 2832 7858 2832 7891, 2832 7892

**Branches :** AHMEDABAD. BENGALURU. BHOPAL. BHUBANESHWAR. COIMBATORE.  
DEHRADUN. DURGAPUR. FARIDABAD. GHAZIABAD. GUWAHATI.  
HYDERABAD. JAIPUR. JAMMU. JAMSHEDPUR. KOCHI. LUCKNOW. NAGPUR.  
PARWANOO. PATNA. PUNE. RAIPUR. RAJKOT. VISAKHAPATNAM.