

नदी घाटी परियोजनाओं के निर्माण,  
प्रचालन और रखरखाव — सुरक्षा  
दिशानिर्देश

भाग 11 भूमिगत उत्खनन  
(पहला पुनरीक्षण)

Construction, Operation and  
Maintenance of River Valley Projects  
— Safety Guidelines

Part 11 Underground Excavation  
( First Revision )



ICS 93.020

© BIS 2023



भारतीय मानक ब्यूरो  
BUREAU OF INDIAN STANDARDS  
मानक भवन, 9 बहादुर शाह ज़फर मार्ग, नई दिल्ली - 110002  
MANAK BHAVAN, 9 BAHADUR SHAH ZAFAR MARG  
NEW DELHI - 110002

[www.bis.gov.in](http://www.bis.gov.in) [www.standardsbis.in](http://www.standardsbis.in)

## FOREWORD

This Indian Standard (Part 11) (First Revision) was adopted by the Bureau of Indian Standards, after the draft finalized by the Safety in Construction, Operation and Maintenance of River Valley Projects Sectional Committee WRD 21, had been approved by the Water Resources Division Council.

With large scale increase in construction activity on river valley projects involving hazardous construction jobs, there has been an increase in the number of accidents, both major and minor ones. Further, increased construction activity in the underground jobs has created health hazards for the persons working under such conditions. In order to minimize such accidents and health hazards, it is the overall responsibility of the project authorities and contractors to provide necessary measures for the safety and health protection of all employees working on the projects.

It shall be the responsibility of the employer that is government or contractor, to initiate and maintain such programs in respect of their employees working on a project scheme.

Each employer/department, contractor and employee shall comply with the different safety regulations in force on a project and shall be alert at all times to eliminate hazards to themselves and/or to others.

This standard was first published in 2012, however, the committee responsible for the formulation of this standard decided to revise it based on the experience gained as well as technological advancements since then.

The following modifications have been incorporated in this revision:

- a) Referred standards have been suitably updated in the present revision;
- b) Clause **3** general safety requirement and **4** investigation, data and surveying have been updated under the requirements;
- c) Title of **5** has been changed from “Design data” to “Planning and Design” and additional clauses suitably incorporated under the requirement;
- d) Title of **6** and its sub clauses have been suitably modified; and
- e) Requirements of rock bolts and Instrumentation have been removed from the standard.

This Indian Standard is published in 11 parts. The other parts in this series are:

- Part 1 General aspects
- Part 2 Amenities, protective clothing and equipment
- Part 3 Plant and machinery
- Part 4 Handling, transportation and storage of explosives
- Part 5 Electrical aspects
- Part 6 Construction
- Part 7 Fire safety aspects
- Part 8 Open excavation
- Part 9 Canals and cross drainage works
- Part 10 Storage, handling, detection and safety measures for gases, chemicals and flammable liquids

The composition of the Committee responsible for the formulation of this standard is given in Annex B.

For the purpose of deciding whether a particular requirement of this standard is complied with the final value, observed or calculated, expressing the result of a test or analysis, shall be rounded off in accordance with IS 2 : 2022 ‘Rules for rounding off numerical values (*second revision*)’. The number of significant places retained in the rounded off value should be the same as that of the specified value in this standard.

*Indian Standard***CONSTRUCTION, OPERATION AND MAINTENANCE OF  
RIVER VALLEY PROJECTS — SAFETY GUIDELINES****PART 11 UNDERGROUND EXCAVATION***(First Revision)***1 SCOPE**

This standard (Part 11) lays down requirements for the safety aspects to be taken during underground excavation for structures like underground power house, transformer cavern, tunnels, shafts such as surge shaft, pressure shaft and cable shaft, additionally driven intermediate tunnels (ADITs) and such other structures associated with river valley projects. Safety measures that should be followed during their operation and maintenance are also described.

**2 REFERENCES**

The standards listed in the Annex A contain provisions which through reference in this text constitute provisions of this standard. At the time of publication, the editions indicated were valid. All standards are subject to revision, and parties to agreements based on these standards are encouraged to investigate the possibility of applying the most recent editions of these standards.

**3 GENERAL SAFETY REQUIREMENTS**

**3.1** The matter of safety and accident prevention is the responsibility of personnel on the job and of the organizations. All persons need to be alert to dangerous conditions and to take necessary precautions for their own safety as well as that of others working at the site.

**3.2** The safety requirement during excavation for any structure may vary according to the type of structure, type of construction methodology, type of strata encountered and number of persons and type of machinery deployed at site.

**3.3** Proper education and organization is necessary for safety requirements to be implemented in a proper manner. The workmen are required to be made aware of the importance of observing the safety rules (*see* also **14**). A security check post shall be maintained at each portal and detailed record of persons/machinery entering/leaving the tunnel shall always be maintained

**3.4** The contractor/owner/department/organization

carrying out the work should employ a safety engineer/manager who should be familiar with all potential hazards on the job and whose duty would be to educate the workmen as well as to supervise installation and maintenance of safety equipment, first aid stations, machinery guards and other safe guards.

**3.5** The hazards of going underground are the greatest the engineer has to face. Underground excavation is always a dangerous and unpredictable business. Hazards cannot be entirely removed, but can be greatly reduced by adopting suitable and adequate precautions.

**4 INVESTIGATION, DATA AND SURVEYING**

**4.1** Before proceeding with the work of underground excavation, sufficient knowledge of sub-surface strata is essential. Insufficient geological data will not only lead to delay in completion of work and increase in cost, but also of a great concern to safety. Geological surprises are to be anticipated and adequate measures for such eventualities should be made available in advance. Planning of underground hydropower projects and tunnels should be based on sufficient geotechnical aspects. This will form the basis of excavation and rock support, etc. Latest advancements should be taken in to consideration.

**4.2** Details of geological strata using mapping methods supplemented by exploratory drilling to establish fissure systems, faults, folds, etc, are essential. The final geological map should provide information on the extent of soil and rock formation, zones of weakness, the dip and strike, etc, of the strata.

**4.3** Adequate measures such as fore poling, pre-grouting, probe hole etc, should be taken for any geotechnical problems in case of blind/unexplored geological regions.

**4.4** Preliminary and detailed surveys should be carried out as per standard practices with modern instruments. During execution of work, accuracy should be maintained in alignment, length and breadth, and levels etc.

## 5 PLANNING AND DESIGN

**5.1** Excavation size is a key parameter in the stability of underground openings in rock and larger the excavation, lesser the stability of roof. The principal objective in the design of a support system is to help the rock mass to support itself. The use of rock bolts helps to form homogeneity in rock mass. The use of rock bolts is a flexible method that can be combined with wire mesh; shotcrete and concrete lining to cope with most situations encountered during underground excavation.

**5.2** A professional engineer should be engaged for preparation of design and drawings. Due consideration in design process should be given to the experience gained in underground works of nearby areas. Field design and changes should be documented and vetted by a competent engineering person.

**5.3** Latest available data from the relevant standards and outputs of nearby seismic stations should also be considered for design of underground structures (*see* IS 4967). Actual data obtained from a nearby strong motion network or micro seismic telemetry network should be considered in seismically active areas/region, if necessary.

**5.4** Tunnel excavation may generate subsidence or deformation around the structure, causing enhanced stress levels. The safety of the existing structures may also be endangered. Special consideration on the safety aspects should be taken in the design/execution.

Execution of earth tunnels/tunnels through soft strata poses a great hazard. Support system and drilling operation should be formulated with extra care and caution [*see* IS 5878 (Part 3)].

**5.5** Safety of tunnel near entry portal with less rock cover should be taken care of during the investigation/design stage itself. Normally the vertical cover should be twice the diameter of the tunnel. If the vertical cover is less than twice the diameter, then cut and cover system should be adopted. Necessary concrete cover at the crown as well as the sides with anchor rods, if necessary, should be provided in the initial stretch from the portal.

**5.6** The arrangement of underground power house and transformer caverns are normally planned adjacent to each other and it should be ensured that there is enough lateral rock cover in-between them for the stability of both the cavities based on the

rock mass characteristics.

## 6 EXECUTIONS

### 6.1 Handling Explosives

During blasting operation proper precautions should be taken for the protection of persons, work and property.

All government laws and regulations relating to the design and location of the explosive magazines, the transportation and the handling of explosives and other measures evolved for the prevention of accidents should be strictly observed. Warning sign of Do's and Don'ts should be displayed on the magazines and warning signal should be given for each blast. Explosive should be stored in a safe place at a sufficient distance from the work site and under the special care of a watchman [*see* IS 10386 (Part 4)].

IS 10386 (Part 4) for handling, transportation and storage of explosives, IS 4081 for blasting and related operations and IS 4138 for working in compressed air, should be strictly adhered to in this regard. Copies of the above standards should be widely circulated and kept available at site office.

**6.1.1** Whenever blasting operation is to be conducted, workmen/supervisors should be kept at sufficient distance in a safe shelter/pocket. Left over and un-blasted detonators should be removed safely. It is to be ensured that no un-blasted detonators are left over in the area before next operations starts. If the hole drilled for blasting is damp, the junction of the fuse and detonators should be made water tight by means of tough grease, white lead or tar. Proper insulated wire should be used for blasting to be carried out by electrical detonators. Electric, non-electric and electronic blasting should be resorted to in all underground works.

### 6.1.2 Precautions Against Lightning

- a) Necessary safety measures should be taken in order to provide protection from direct stroke lightning and secondary action of the lightning; and
- b) During a thunderstorm, no blasting operation including charging should be carried out. If in case of electrical shot-firing, the firing circuit has to be set-up before thunderstorm appears and the blast lines should be disconnected from the trunk line and thoroughly insulated with tape. At the same time, all persons must be withdrawn from the danger zone.

## 6.2 Blast Vibration Monitoring

Monitoring the vibrations caused by underground blasting plays a vital role since they induce transient or vibratory displacements which could be permanent (*see* IS 14881).

**6.2.1** Tunnel face stability is a severe problem while tunneling, especially in non-cohesive strata. Buildings and services over the excavation and the workers inside the tunnel are under continuous risk due to this problem. There may be sudden falls of soil, creating large cave-ins up to the surface. Falling material could endanger workers. Such endangered areas should be supported, barricaded or effectively guarded.

**6.2.2** Safety of tunnel entry near portal with less rock cover should be taken care of during the investigation/design stage itself. Normally the soil cover should be twice the diameter of the tunnel. If the overburden is less than twice the diameter, then cut and cover system should be adopted. Necessary concrete cover at the crown as well as the sides with anchor rods, if necessary, should be provided in the area not having adequate cover.

## 6.3 Rock Bursting

The energy within the rock, as inherent stresses begin to relax on excavation, can be enormous and powerful enough to expel large chunks of rock causing rock burst/spalling. There are various methods for determining the rock pressure for support design of underground excavation which should be utilized.

## 6.4 Excavation Slope

The slopes in the underground excavation such as pressure shafts, etc, should be decided on suitable engineering practice based on the geological strata, geo-techniques and geo-physical data.

### 6.4.1 Sequence of Excavation

Sequence of excavation should be carefully planned, specifying the charge and strength of explosives. Where multiple work fronts/junctions exist involving crossing over of components, abundant care should be exercised in blasting operation and mucking and guiding the vehicles /equipment.

## 6.5 Disposal of Excavated Earth/Muck

**6.5.1** Excavated muck should be cleared as soon as the excavation process of each cycle is completed and de-fuming has been done. The free-falling muck in the pressure shafts should be removed as frequently as possible, otherwise it may choke up

the shafts. Choking of the lower end of the shaft may cause the mucking operations to prove hazardous to the mucking crew and the equipment. After the blasting and before mucking is started, the pollution should be checked on face of mucking as per relevant Indian Standards. Radioactive pollution, if any, should be checked for permissible limits.

**6.5.2** No inflammable materials or oil and grease should be stored inside or near the tunnels or shafts and all combustible rubbish from the tunnel or shaft should be promptly removed.

## 6.6 Overhangs

**6.6.1** Overhangs in the excavated face are hazardous as these may come down unexpectedly and result in fatal accidents to persons working at lower levels. Hence, such overhangs should be removed before continuation of further work in that area. Adequate precautions should be taken while removing the overhangs.

**6.6.2** All excavated faces, on which work is in progress or work is temporarily suspended, should be maintained or left at safe slopes, so that the danger caused by caving or sliding is eliminated.

## 6.7 Service Lines

Service lines, such as power cable, water line, air line, dewatering line, etc, of the owner and contractor, should be segregated and laid/run on opposite face of the tunnel/cavern.

### 6.7.1 Power Lines

Live wires and cables are laid in the area of excavation for blasting operations, drilling of holes and other operations involving the use of electric power. Where such cables are laid, care should be taken to see that these cables are not laid haphazardly. The supervisors, foreman and the construction staff should ensure that workmen or visitors are kept away from live wires. Wherever necessary, warning signals should be posted. Cables which are cut or open should be promptly replaced [*see* IS 10386 (Part 5)]. All electric wiring should be properly insulated and of sufficient capacity supported on insulators of approved type and not looped on or tied to spikes, ventilating pipes, or other makeshift supports. All switches should be of automatic trip type. Lines should be located so as not to create any electricity or tripping hazard to workers.

### 6.7.2 Water Lines

Water lines are laid for different purposes such as

drinking water, firefighting, construction purpose, etc. Each line should be properly distinguished by a system of colour coding as per the relevant Indian Standards and should be well maintained.

### 6.8 Lighting, Warning Signals, etc

**6.8.1** Adequate lighting arrangements should be provided at the underground excavation worksite in the access tunnel, ADITs (additionally driven intermediate tunnels), pathways.

**6.8.2** Danger lights should be provided at machinery locations and turning points in the access path for guidance of transport vehicles. At bend/crossings of pathways/roadway proper indications should be displayed.

**6.8.3** Whenever a workman is required to climb up/down on an excavation slope for working on shuttering, reinforcement at shafts, inclined tunnels, etc, he/she should do so with a safety rope tied securely to a safety belt and wearing safety helmet. Safety net should be provided below the work spot.

**6.8.4** Single person should not be permitted in the area of underground excavation alone. All entry and exits that is, check-in and check-out times should be recorded.

**6.8.5** Flame-proof electrical installations shall be used in situation where methane or other flammable gas is encountered.

### 6.9 Dewatering

**6.9.1** During excavation work, adequate arrangements should be provided for dewatering and bailing out water from the excavated area to prevent slippery surfaces and sliding of slopes due to standing water.

**6.9.2** Adequate measures should be taken to drain away the water from the upper surfaces of excavated slopes or benches. This prevents saturation of soil which could result in slips of the excavated slopes.

**6.9.3** Temporary drainage system as well as permanent ones, such as ducts, should be constructed.

**6.9.4** Necessary full-proof reliable arrangements should be made so that the surface/storm water from valleys nearby tunnels, shafts, additionally driven intermediate tunnel (ADIT), etc, do not gain entry into the work area. In pumped storage power houses there is always a threat of flooding if there is leakage or damage to the draft tube gate. Pumps alone may not be able to pump out the

water and provision of drainage tunnels to nearby valleys should be considered.

**6.9.5** Drainage holes should be provided in the crown, as well as on either side of the cavern, shafts, etc, so that the seepage water can be drained through these holes.

**6.9.6** Following measures should be taken whenever adverse geo-thermal conditions are encountered during underground excavation:

- a) Monitoring of temperature inside the tunnel especially where rock cover is very high and where there is history or evidence of occurrence of hot water springs;
- b) Provision of additional ventilation including blowing of cool air, etc, at work site;
- c) Provision of ice-jackets to workers; and
- d) Reduced working hours inside the cavern.

### 6.10 Ventilating the Tunnel

- a) Ventilating duct/pipe of suitable diameter as per approved norms should be provided inside the tunnel for diffusing the fumes after blasting;
- b) In addition to the ventilating pipe, a sufficient supply of fresh air should be provided at all times, in all places underground and provision should be made for quick removal of toxic gases and dust;
- c) The concentration of various gases inside the tunnel should adhere to the limits given in 7.2.2 of IS 4756; and
- d) Provision for additional ventilation may be made in situation where methane or other flammable gas is encountered.

### 6.11 Noise Control

**6.11.1** The noise pollution should be controlled:

- a) At the source;
- b) By enclosure;
- c) By sound absorbing materials; and
- d) By ear protection.

**6.11.2** Control of noise by ear protection should be affected by the following methods depending upon the sound intensity level of the noise:

- a) Cotton;
- b) Impregnated cotton;
- c) Soft rubber;
- d) Muffs and helmets; and
- e) Any of the above combinations.

### 6.11 Welding

Welding equipment and the structure to be welded should be properly earthed. General exhaust system should be available to take care of the evacuation of fumes. Unused gas cylinders should be kept at a safe place.

No welding should be done when concentration of methane or other flammable gases are encountered.

### 6.12 Winch/Wire Rope

Winch is an important equipment which conveys persons and material. It should be operated and maintained with extreme care and caution. Periodical checks for the wire rope, gear box, braking system etc, should be carried out as per relevant standards where exist.

Inspection of the wire rope system should be carried out as frequently as possible to locate any kinking, twisting of rope, loosening of the strands and any other damage. Obstruction in the movement of the rope/wires should be eliminated to avoid accident.

Log books should be maintained properly recording hours of operation, details of trips, number of persons and load carried, problems noticed, repairs carried out, periodical inspections, mandatory checks and maintenance works.

There should not be any overlapping of wire ropes in the winch drums which may lead to sudden fall/jerk of the winch/jhula in the shaft. This sudden jerk of winch may hit the side rock in the case of small diameter shafts such as power cable shaft, ventilation shafts leading to serious accidents. Comparatively, confined space creates a hazard.

The following Indian Standards may be referred for material of different components of winch and for its maintenance:

Steel-wire rope	:	IS 2266
Maintenance of wire rope	:	IS 3973
Preferred size for wrought metal products (trolley wheels)	:	IS 1136
Gears	:	IS 2458 IS 2467 IS 2535 (Part 1) IS 2535 (Part 2) and IS 4460 (Parts 1 to 3)
Motor	:	IS 12615
Socketing of wire rope with molten metal	:	IS 3937 (Parts 1 to 3)

### 6.13 Tools, Plant and Machinery

Proper care should be taken in the operation and maintenance of transport vehicles such as loaders, dumpers, tippers and trailers, cranes/winches.

Numbers of serious accidents have been associated with transport. The use of trucks/wagons and heavy machinery should be done under the supervision of experienced personnel. Care should be exercised when guiding vehicles for loading so that they don't collide with side cutting and other vital installations such as cables, lights, ventilation ducts, pumps etc. Vehicle pockets should be provided at suitable intervals (say every 750 m) along the tunnel.

The underground excavation of inclined shaft is normally done by raise climber or similar machine. Great care should be taken in the operation and maintenance of such machines [see IS 10386 (Part 3) and IS 7293].

### 6.14 Access and Escape Ways

**6.14.1** Pathways, if required, should be non-slippery and of adequate width. They should be strong enough to withstand the movement of workers and hand carried tools and equipment.

**6.14.2** Gangways, if required, should be strong and of proper construction. Planks used should be of uniform and sufficient thickness and free from knots. Gangways should be kept clear of excavated materials or other obstruction.

**6.14.3** Proper level steps should be provided where the gradient of roadway exceeds 15°. It is desirable that proper steps be provided in wet and/or slippery roadways, irrespective of the gradient of such roadways, so that the workers can conveniently use protective footwear even under adverse conditions.

**6.14.4** Escape routes from different sections or parts of underground power house, underground transformer cavern, tunnels, etc, should be prominently designated by suitable markings so that they are clearly visible underground. This is in addition to the usual mock drills/rehearsals once in a quarter.

## 7 TUNNEL WATERPROOFING

**7.1** One of the most persistent problems encountered both during construction and the operation of any tunnel is that of water leakage/seepage.

**7.2** Primary and secondary linings are the main defense against water ingress or leakage but these

can be weakened by a faulty method. Grouting techniques and grout composition have become extremely sophisticated during the past few years with the development of modern injection techniques as well as the growing use of additives, such as resins and plasticizers and these should be considered for use appropriately.

## **8 WATER CONDUCTOR SYSTEM — SAFE FILLING AND EMPTYING**

During these operations, the stresses in surrounding rock mass of water conductor system gets increased, released or rearranged. These are critical operations involving high risk and due processes. Safeguards should be followed as detailed in IS 12633.

## **9 FAILURES**

In certain sections, although the supports are provided as per the rock conditions as stated by the designers, failure of roof and side walls may occur in the form of falling blocks, roof cave-in, crown settlement, buckling of ribs, shotcrete cracking, etc. The possible causes of failure in certain sections could be due to the following:

- a) Assumption of improper classification of the rock by the wrong choice of support for identified rock class;
- b) Insufficient thickness of applied shotcrete layer;
- c) Incorrect rock bolting pattern and/or insufficient number of rock bolts;
- d) Shotcreting applied after considerable delay that is after loosening of surrounding rock mass, insufficient shotcrete in crown, initial layer of shotcrete omitted;
- e) Steel supports not positioned properly and no backfilling behind the steel support;
- f) Non-identification of rock blocks/wedges which are free to fall or free to slide under their own weight;
- g) Failure to insert rock bolts to stabilize the rock;
- h) Additional layer of shotcrete omitted in weak ground; and
- j) Incorrect grouting of rock bolts and untensioned rock bolts.

## **10 EMERGENCY PLANNING**

**10.1** Workers at the face of a long tunnel are deprived of quick access to a medical center. For this, each member of the work force should be given at least some basic first-aid training. A special team of highly trained advanced first aiders is also essential. They should be provided with

first-aid kits. Presence of doctors in project area is also important. Safety officers, with a mines safety background, should inspect machinery, monitor for hazards and give regular instruction on safe methods.

When there is a fatality or serious untoward incident, each such occurrence should be thoroughly investigated and the management should decide on how to deal with such situation and to avoid re-occurrence of a similar incident. It is essential for immediate shut down and examination of machinery and all similar equipment involved.

In case of major accidents, it is also necessary to inform immediately various levels of management, nearby disaster management agency, in addition to fire and rescue team. The respective contact numbers should be readily available and displayed. Review meetings should be held as frequently as possible to sort out and plan for any shortcoming.

### **10.2 Means of Exit/Escape**

During excavation work, adequate means of exit/escape for work force from the hazardous areas/situations should be planned, and kept clear.

### **10.3 Evacuation Plan**

Suitable evacuation plan, should be planned and made known to all the personnel involved in underground excavation work.

### **10.4 Communication**

Reliable communication system should be maintained during and after excavation work. It is desirable to have loud phones or megaphones readily available for announcement of any impending emergency like fire, collapse, etc.

## **11 HEALTH AND SAFETY**

Supervisory health and safety course should be conducted and attended by engineers /supervisor/foremen. Written check lists should be displayed at all work locations for compliance.

The rescue team should be highly trained and well equipped. Proper personal protective equipment should be made available to operators. The level of diesel fumes within underground excavation area should be closely monitored by gas analyzer.

## **12 PERIODIC INSPECTION**

Periodic inspection of underground excavation areas after commissioning of power house plays a vital role and should be made mandatory specifying



periodicity. Necessary periodic maintenance of ladders, landing platforms, top cover grills of various shafts, lining in tunnels, winches for shafts, etc, are very important in the long run. Vegetation growth in the unlined shafts, etc, should be completely cleared. After commissioning, the tunnels, shafts, underground power house and transformer cavern side walls, roof, etc, should be periodically inspected and repairs attended to immediately during shut down period, etc.

### 13 COMMUNICATION

Proper communication system should be established to facilitate communication between workplace and the management, worker and the safety manager and between various work fronts. Walkie-talkie, wireless mike system and similar equipment should be installed. Close circuit TV should also be installed to keep watch of critical components, critical locations, auxiliaries, cable routes, transformer cavern and other vulnerable areas.

### 14 SAFETY OFFICER

It is essential to employ a qualified safety officer/engineer-in-charge to supervise the safety measures and to ensure the safety of personnel, employees, workers employed at site of underground excavation, equipments, during the excavation, operation and maintenance period also.

The duties of the safety engineer/manager/officer are given below:

- a) To impart education and training to the workers and employees engaged in the underground excavation works;
- b) To comply with relevant safety rules and regulations;
- c) To undertake all steps to reduce risk to employees, property, machine and surrounding areas;
- d) To check all machine, equipment, firefighting water piping system, electrical appliances, first-aid station and to keep them in good working condition;
- e) To take immediate action during any emergency situation, floods, etc;
- f) Sustaining the efforts and continual improvements;
- g) To evolve safety planning and conduct review meeting with site management, contractors and workers;
- h) To arrange for displaying the warning signals/boards at vulnerable area;
- j) To avoid excessively and unnecessary strenuous work position and movement;

- k) To conduct internal safety audit half yearly/annually, and to conduct external safety audit twice or thrice during the excavation process;
- m) To prepare safety manuals for each specific component; and
- n) To ensure mandatory inspection and compliance and monitoring at higher management levels.

### 14.1 Accident Reporting

Any accident fatal/non-fatal (injuries) should be reported to the top management and law enforcing authorities within a time frame as below:

Reporting time :

Fatal	:	Immediate (detailed report should follow)
Non-fatal	:	Within 3 days
Damage to costly equipment	to :	Within 2 days (preliminary report) and detailed report after due inspection of experts and assessment

### 14.2 Cause for Accidents

Cause for accident should be reviewed/ investigated and remedial measures monitored. Necessary safety measures should be adopted. Existing measures, if found deficient, should be modified and corrected and suitable guidelines should be issued, to avoid reoccurrence.

### 14.3 Disaster Management

Close co-ordination should be maintained with the district disaster management authority at all times especially at the aftermath of occurrence of fatal accidents, floods, fire, epidemics and other natural calamities.

### 15 FIRE RISK

Smoking by workers increases the risk of fire. Smoking should be strictly prohibited in work spot. Cooking in and around the vicinity of work place should be prohibited. As there is danger of fire and smoke resulting from rubbish, litter during construction operations, they should be removed and taken out in every shift. Safety code for electrical aspects [IS 10386 (Part 5)] and for fire safety [IS 10386 (Part 7)] should be adhered to.

#### 15.1 Fire Alarm/Smoke Detection Alarm System

After excavation work, vulnerable areas in the underground space should be provided with automatic fire detection and alarm system (including manual fire alarm call points)

conforming to IS 2189.

### **15.2 Extinguishers**

Fire extinguishers, of various types, suitable for the areas of fire risk covered should be provided in conformity with IS 2190.

### **16 VISITORS**

Visitors should not be permitted to enter the area of underground excavation. In unavoidable cases, they should be accompanied by a supervisor. They should be kept at sufficient distance from the cutting edge, running machinery and other potentially dangerous areas. All visitors should be provided with safety gadgets, and their details noted in the entry register. Details of all persons including workers/supervisors, their time of entry into the site and exit should be recorded.

### **17 BUDGET**

As the safety aspects of underground structures are of paramount concern to the nation/state/owner, the safety system should be kept alert and reliable and a reasonable budget provision should be allocated, especially during the maintenance period.

### **18 DOCUMENTATION**

Proper documents should be prepared indicating problems encountered during the excavation works, such as accidents, flooding, rock fall, if any, and other difficulties encountered during excavation etc. The outcome and action taken on periodic inspections should also be documented. This document will be useful for future underground excavation works.

## ANNEX A

(Foreword)

## LIST OF REFERRED STANDARDS

<i>IS No.</i>	<i>Title</i>	<i>IS No.</i>	<i>Title</i>
IS 1136 : 2008	Preferred sizes for wrought metal products ( <i>third revision</i> )	IS 4138 : 1977	Safety code for working in compressed air ( <i>first revision</i> )
IS 2189 : 2008	Selection, installation and maintenance of automatic fire detection and alarm system — Code of practice ( <i>fourth revision</i> )	IS 4460 (Part 1 to 3) : 1995	Gears — Spur and helical gears — Calculation of load capacity ( <i>first revision</i> )
IS 2190 : 2010	Selection, installation and maintenance of first-aid fire extinguishers — Code of practice ( <i>fourth revision</i> )	IS 4756 : 1978	Safety code for tunneling work ( <i>first revision</i> )
IS 2266 : 2019	Steel wire ropes for general engineering purposes — Specification ( <i>fifth revision</i> )	IS 4967 : 1968	Recommendations for seismic instrumentation for river valley projects
IS 2458 : 2001/ ISO 1122-1 : 1998	Vocabulary of gear terms — Definitions related to geometry ( <i>first revision</i> )	IS 5878 (Part 3) : 1972	Code of practice for construction of tunnels: Part 3 Underground excavation in soft strata
IS 2467 : 2002/ ISO 701 : 1998	International gear notation — Symbols for geometrical data ( <i>first revision</i> )	IS 7293 : 1974	Safety code for working with construction machinery
IS 2535	Cylindrical gears for general and heavy engineering:	IS 10386	Safety code for construction, operation and maintenance of river valley projects:
(Part 1) : 2004/ ISO 53 : 1998	Standard basic rack tooth profile ( <i>third revision</i> )	(Part 3) : 2014	Plant and machinery ( <i>first revision</i> )
(Part 2) : 2004/ ISO 54 : 1996	Module ( <i>third revision</i> )	(Part 4) : 2013	Handling, transportation and storage of explosives ( <i>first revision</i> )
IS 3937	Recommendations for socketing of wire ropes:	(Part 5) : 2014	Electrical aspects ( <i>first revision</i> )
(Part 1) : 2022	Socketing with zinc ( <i>second revision</i> )	(Part 7) : 2020	Fire safety aspects ( <i>first revision</i> )
(Part 2) : 2022	Socketing with white metal ( <i>second revision</i> )	IS 12615 : 2018	Line operated three phase A.C. motors (IE Code) “Efficiency classes and performance specification” ( <i>third revision</i> )
(Part 3) : 2022	Socketing with resins ( <i>first revision</i> )	IS 12633 : 1989	First filling and emptying of pressure tunnels — Guidelines
IS 3973 : 2022	Code of practice for the selection, installation and maintenance of wire ropes ( <i>second revision</i> )	IS 14881 : 2001	Method for blast vibration monitoring — Guidelines
IS 4081 : 2013	Blasting and related drilling operations — Code of safety ( <i>second revision</i> )	IS 15026 (Part 1) : 2002	Tunnelling in rock masses — Guidelines: Part 1 Conventional tunnelling methods

## ANNEX B

(Foreword)

## COMMITTEE COMPOSITION

Safety in Construction, Operation and Maintenance of River Valley Projects Sectional Committee, WRD 21

<i>Organization</i>	<i>Representative(s)</i>
National Hydroelectric Power Corporation, Faridabad	SHRI RAJESH SHARMA ( <i>Chairperson</i> )
Bhakra Beas Management Board, Chandigarh	MEMBER IRRIGATION ER ARVIND KUMAR SHARMA ( <i>Alternate</i> )
Bharat Heavy Electrical Limited, New Delhi	SHRI V. SHRINIVAS RAO SHRI RAGHVENDRA SINGH ( <i>Alternate</i> )
Central Board of Irrigation and Power, New Delhi	SHRI K. K. SINGH SHRI SUNIL SHARMA ( <i>Alternate</i> )
Central Electricity Authority, New Delhi	SHRI MANOJ TRIPATHI SHRI RAJEEV VARSHNEY ( <i>Alternate</i> )
Central Water Commission, New Delhi	SHRI AMIT KUMAR JHA SHRI P. N. SINGH ( <i>Alternate</i> )
Centre for Fire and Explosive Environment Safety, Defence Institute of Fire Research, Delhi	DR P. K. RAI
Geological Survey of India, New Delhi	SHRI MANOJ KUMAR KAISTHA SHRI NIHAR RANJAN ( <i>Alternate</i> )
HCC Limited, New Delhi	SHRI SANAJY Dave SHRI SHARAD GOEL ( <i>Alternate I</i> ) SHRI ATUL MANIKKULE ( <i>Alternate II</i> )
Himachal Pradesh Power Corporation Limited, Shimla	ER R. K. KAUNDAL ER SANJAY RANA ( <i>Alternate</i> )
Indian Institute of Technology Roorkee, Roorkee	PROF S. K. SINGAL PROF M. K. SINGHAL ( <i>Alternate</i> )
Irrigation Department Government of Andhra Pradesh	SHRI A. SURI BABU
Irrigation Department Government of Maharashtra	SUPERINTENDING Engineering, DSO SHRI VIKANT ANAND ( <i>Alternate</i> )
Irrigation Department Government of Punjab, Chandigarh	CHIEF ENGINEER (RSDD) DIRECTOR DAMS (RSDD) ( <i>Alternate</i> )
Larsen and Toubro Limited, Mumbai	SHRI AMAR PAL SINGH SHRI SANJAY PAJNI ( <i>Alternate</i> )
National Hydroelectric Power Corporation, Faridabad	SHRI AMIT KUMAR SHRI BRAJNANDAN RAM ( <i>Alternate I</i> ) SHRI NEERAJ KUMAR ( <i>Alternate II</i> )
National Projects Construction Corporation Limited, Faridabad	SHRI D. P. SINGH SHRI RISHIN MANAS DAS ( <i>Alternate</i> )
National Water Development Agency, New Delhi	SHRI D. K. SHARMA SHRI S. C. AWASTHI ( <i>Alternate</i> )

<i>Organization</i>	<i>Representative(s)</i>
North Eastern Electric Power Corporation Limited, Shillong	SHRI D. DAS
SJVN Limited, Shimla	SHRI ARVIND MAHAJAN SHRI AJAY UPPAL ( <i>Alternate</i> )
Sardar Sarovar Narmada Nigam Limited, Gandhinagar	SHRI K. B. PARMAR SUPERINTENDING ENGINEER ( <i>Alternate</i> )
Tamil Nadu Generation and Distribution Corporation Limited, Chennai	SHRI V. GOPALAKRISHNAN
Uttarakhand Jal Vidyut Nigam Limited, Dehradun	GENERAL MANAGER (LD & J)
Water Resources Department, Government of Madhya Pradesh, Bhopal	SHRI B. C. PURANDARE SHRI R. K. JAIN ( <i>Alternate</i> )
Gujarat Engineering research institute, Vadodara	SHRI B. H. CHAUDHARI SHRI P. P. BUTANI ( <i>Alternate</i> )
SOMA Enterprise Ltd, Hyderabad	SHRI BISWAJIT DAS SHRI BAPPANA JAGADISH KUMAR ( <i>Alternate</i> )
National Safety Council, Mumbai	SHRI SANDEEP DHAMONE SHRI AKSHAY V. HOTKAR ( <i>Alternate</i> )
Narmada Hydroelectric Development Corporation limited	SHRI JAI PRAKASH SHRI SHASHANK SHUKLA ( <i>Alternate</i> )
In Personal Capacity ( <i>SB 184, Anandam NTPC</i> )	SHRI A. B. LAL
In Personal Capacity ( <i>Flat No. 3/103, Deepak Jankipuram, Sahara States, Nr. LP School, Lucknow</i> )	SHRI ASHOK KUMAR PRASAD
BIS Director General	SHRI R. BHANU PRAKASH, SCIENTIST 'E'/DIRECTOR AND HEAD (WATER RESOURCES) [REPRESENTING DIRECTOR GENERAL ( <i>Ex-officio</i> )]

*Member Secretary*  
SHRI AJAY MEENA  
SCIENTIST 'B'/ASSISTANT DIRECTOR  
(WATER RESOURCES), BIS





## Bureau of Indian Standards

BIS is a statutory institution established under the *Bureau of Indian Standards Act, 2016* to promote harmonious development of the activities of standardization, marking and quality certification of goods and attending to connected matters in the country.

### Copyright

BIS has the copyright of all its publications. No part of these publications may be reproduced in any form without the prior permission in writing of BIS. This does not preclude the free use, in the course of implementing the standard, of necessary details, such as symbols and sizes, type or grade designations. Enquiries relating to copyright be addressed to the Head (Publication & Sales), BIS.

### Review of Indian Standards

Amendments are issued to standards as the need arises on the basis of comments. Standards are also reviewed periodically; a standard along with amendments is reaffirmed when such review indicates that no changes are needed; if the review indicates that changes are needed, it is taken up for revision. Users of Indian Standards should ascertain that they are in possession of the latest amendments or edition by referring to the website-[www.bis.gov.in](http://www.bis.gov.in) or [www.standardsbis.in](http://www.standardsbis.in).

This Indian Standard has been developed from Doc No.: WRD 21 (12904).

### Amendments Issued Since Publication

Amend No.	Date of Issue	Text Affected

## BUREAU OF INDIAN STANDARDS

### Headquarters:

Manak Bhavan, 9 Bahadur Shah Zafar Marg, New Delhi 110002

Telephones: 2323 0131, 2323 3375, 2323 9402

Website: [www.bis.gov.in](http://www.bis.gov.in)

### Regional Offices:

	Telephones
Central : 601/A, Konnectus Tower -1, 6 <sup>th</sup> Floor, DMRC Building, Bhavbhuti Marg, New Delhi 110002	{ 2323 7617
Eastern : 8 <sup>th</sup> Floor, Plot No 7/7 & 7/8, CP Block, Sector V, Salt Lake, Kolkata, West Bengal 700091	{ 2367 0012 2320 9474
Northern : Plot No. 4-A, Sector 27-B, Madhya Marg, Chandigarh 160019	{ 265 9930
Southern : C.I.T. Campus, IV Cross Road, Taramani, Chennai 600113	{ 2254 1442 2254 1216
Western : Plot No. E-9, Road No.-8, MIDC, Andheri (East), Mumbai 400093	{ 2821 8093

**Branches :** AHMEDABAD. BENGALURU. BHOPAL. BHUBANESHWAR. CHANDIGARH. CHENNAI. COIMBATORE. DEHRADUN. DELHI. FARIDABAD. GHAZIABAD. GUWAHATI. HIMACHAL PRADESH. HUBLI. HYDERABAD. JAIPUR. JAMMU & KASHMIR. JAMSHEDPUR. KOCHI. KOLKATA. LUCKNOW. MADURAI. MUMBAI. NAGPUR. NOIDA. PANIPAT. PATNA. PUNE. RAIPUR. RAJKOT. SURAT. VISAKHAPATNAM.